BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work:Asphalting to roads at Sai Archade,G Ramaiah, and surrounding areas in ward no -03 Yelahanka Satellite Town sub Division

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
		Estimate Cost Rs.							20000000
1	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. P No. 143/ Item No. 19.1/ PWD SR 2018-19								
	RCC Drain	Cum							
	G Ramaiah Layout								
	1st Cross Road								
	LHS								
	RHS		1	50.5	1.1	1	55.55		
	2nd Cross Road		1	109	1.1	1	119.9		
	LHS								
	RHS		1	92.5	1.1	1	101.75		
	3rd Cross Road		1	113.9	1.1	1	125.29		
	LHS								
	RHS		1	138	1.1	1	151.8		
	4th Cross Road		1	128	1.1	1	140.8		
	LHS								
	RHS		1	119	1.1	1	130.9		
	4th A Cross Road		1	146.9	1.1	1	161.59		
	LHS								
	RHS		1	22	1.1	1	24.2		
	4th B Cross Road		1	25.5	1.1	1	28.05		
	LHS								
	RHS		1	44	1.1	1	48.4		
	Drain Desilt		1	47.5	1.1	1	52.25		
	G Ramaiah Layout								
	1st Cross Road								
	LHS		1	74.7	0.5	0.4	14.94		
	RHS		1	8.9	0.5	0.4	1.78		
	2nd Cross Road								
	LHS		1	37.5	0.5	0.3	5.63		
	RHS		1	13.9	0.6	0.3	2.50		
	3rd Cross Road								
	LHS		1	19	0.6	0.4	4.56		
	4th Cross Road								
	LHS		1	29	0.6	0.4	6.96		
	RHS		1	6.5	0.6	0.4	1.56		
						Cum	1178.41	211.79	249572.00
	Basic Rate	130.00							
	Loading and Unloading Charges	57.00							
	5km Lead	12.80							
	Sub total	199.80							
	Area Weightage @ 6%	11.99							
	Total	211.79							
2	KSRRB M2900-1. Plain cement concrete M10 mix with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 408								
	RCC Drain	Cum							
	G.Ramaiah Layout								
	1st Cross Road								
	LHS		1	50.5	1.1	0.15	8.33		
	RHS		1	109	1.1	0.15	17.99		
	2nd Cross Road								
	LHS		1	92.5	1.1	0.15	15.26		
	RHS		1	113.9	1.1	0.15	18.79		
	3rd Cross Road								
	LHS		1	138	1.1	0.15	22.77		
	RHS		1	128	1.1	0.15	21.12		
	4th Cross Road								
	LHS		1	119	1.1	0.15	19.64		
	RHS		1	146.9	1.1	0.15	24.24		
	4th A Cross Road								
	LHS		1	22	1.1	0.15	3.63		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	RHS								
	4th B Cross Road		1	25.5	1.1	0.15	4.21		
	LHS								
	RHS		1	44	1.1	0.15	7.26		
	Drain Bottom (Vent Concrete)		1	47.5	1.1	0.15	7.84		
	G Ramaiah Layout								
	1st Cross Road								
	LHS								
	RHS		1	74.7	0.55	0.15	6.16		
	2nd Cross Road		1	8.9	0.55	0.15	0.73		
	LHS								
	RHS		1	37.5	0.55	0.15	3.09		
	3rd Cross Road		1	13.9	0.55	0.15	1.15		
	LHS								
	4th Cross Road		1	19	0.55	0.15	1.57		
	LHS								
	RHS		1	29	0.55	0.15	2.39		
	Kerb PCC		1	6.5	0.56	0.15	0.55		
	1st Cross Road								
	LHS								
	RHS		1	90.3	0.2	0.1	1.81		
	2nd Cross Road		1	109	0.2	0.1	2.18		
	LHS								
	RHS		1	102.5	0.2	0.1	2.05		
	3rd Cross Road		1	113.9	0.2	0.1	2.28		
	LHS								
	RHS		1	157	0.2	0.1	3.14		
	4th Cross Road		1	128	0.2	0.1	2.56		
	LHS								
	RHS		1	119	0.2	0.1	2.38		
	4th A Cross Road		1	146.9	0.2	0.1	2.94		
	LHS								
	RHS		1	22	0.2	0.1	0.44		
	4th B Cross Road		1	25.5	0.2	0.1	0.51		
	LHS								
	RHS		1	44	0.2	0.1	0.88		
	Subash Chandra Bose Layout,Sai Nagar		1	47.5	0.2	0.1	0.95		
	5th Cross Road								
	LHS		1	115	0.2	0.1	2.30		
	RHS		1	115	0.2	0.1	2.30		
	6th Cross Road								
	LHS		1	125	0.2	0.1	2.50		
	RHS		1	120	0.2	0.1	2.40		
	3rd Cross Road BHEL Layout								
	RHS		1	120	0.2	0.1	2.40		
	Subash Chandra Bose Layout,Sai Nagar Main Rd								
	RHS		1	30	0.2	0.1	0.60		
						Cum	221.33	4479.56	991450.00
	Basic Rate	4,226.00							
	Area Weightage @ 6%	253.56							
	Total	4479.56							
3	KSRB 4.2.2 : Providing and laying in position **plain cement concrete of mix M20** withOPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.43cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc, complete excluding cost of stell as per MORTH specification NO. 1500, 1700, 2200. Including cost of materials, labour, HOM complete as per specifications. Item No. 37.59.2/ page no:271/PWD SR 2018-19								
	RCC Drain	Cum							
	G.Ramaiah Layout								
	Raft								
	1st Cross Road								
	LHS		1	50.5	0.9	0.15	6.82		
	RHS		1	109	0.9	0.15	14.72		
	2nd Cross Road								
	LHS		1	92.5	0.9	0.15	12.49		
	RHS		1	113.9	0.9	0.15	15.38		
	3rd Cross Road								
	LHS		1	138	0.9	0.15	18.63		
	RHS		1	128	0.9	0.15	17.28		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	4th Cross Road								
	LHS		1	119	0.9	0.15	16.07		
	RHS		1	146.9	0.9	0.15	19.83		
	4th A Cross Road								
	LHS		1	22	0.9	0.15	2.97		
	RHS		1	25.5	0.9	0.15	3.44		
	4th B Cross Road								
	LHS		1	44	0.9	0.15	5.94		
	RHS		1	47.5	0.9	0.15	6.41		
	Wall								
	1st Cross Road								
	LHS		2	50.5	0.15	0.55	8.33		
	RHS		2	109	0.15	0.55	17.99		
	2nd Cross Road								
	LHS		2	92.5	0.15	0.6	16.65		
	RHS		2	113.9	0.15	0.6	20.50		
	3rd Cross Road								
	LHS		2	138	0.15	0.6	24.84		
	RHS		2	128	0.15	0.6	23.04		
	4th Cross Road								
	LHS		2	119	0.15	0.6	21.42		
	RHS		2	146.9	0.15	0.6	26.44		
	4th A Cross Road								
	LHS		2	22	0.15	0.58	3.83		
	RHS		2	25.5	0.15	0.6	4.59		
	4th B Cross Road								
	LHS		2	44	0.15	0.6	7.92		
	RHS		2	47.5	0.15	0.6	8.55		
						Cum	324.08	7070.2	2291310.00
	Basic Rate	6670.00							
	Area Weightage @ 6%	400.20							
	Total	7070.20							
4	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio (I No-28.8.2,P No-229)								
	RCC Drain	Tonne							
	Steel For Drain		56	324.08			18148.48		
						Tonne	18.15	72326.98	1312625.00
	Basic Rate	68233.00							
	Area Weightage @ 6%	4093.98							
	Total	72326.98							
5	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (Page No 27., I.No.5.33 of KPWD S.R 2018-19).								
		Sqm							
	G.Ramaiah Layout								
	1st Cross Road								
	LHS		1	73	0.9		65.70		
	RHS		1	31.25	0.9		28.13		
	2nd Cross Road								
	LHS		1	45.67	0.9		41.10		
	RHS		1	31.6	0.9		28.44		
	3rd Cross Road								
	LHS		1	33.2	0.9		29.88		
	RHS		1	30.5	0.9		27.45		
	4th Cross Road								
	LHS		1	12.5	0.9		11.25		
	RHS		1	6.5	0.9		5.85		
	4th A Cross Road								
	LHS		1	11	0.9		9.90		
	RHS		1	12	0.9		10.80		
	4th B Cross Road								
	LHS		1	14	0.9		12.60		
						Sqm	271.10	111.30	30173.00
	Basic Rate	105.00							
	Area Weightage @ 6%	6.30							
	Total	111.30							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
6	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	G.Ramaiah Layout	Sqm							
	1st Cross Road								
	LHS								
	RHS		1	47	0.9		42.30		
	2nd Cross Road		1	86.45	0.9		77.81		
	LHS								
	RHS		1	69.9	0.9		62.91		
	3rd Cross Road		1	96.65	0.9		86.99		
	LHS								
	RHS		1	124.8	0.9		112.32		
	4th Cross Road		1	92	0.9		82.80		
	LHS								
	RHS		1	133.5	0.9		120.15		
	4th A Cross Road		1	125.9	0.9		113.31		
	LHS								
	RHS		1	24	0.9		21.60		
	4th B Cross Road		1	38	0.9		34.20		
	LHS								
	RHS		1	6	0.9		5.40		
			1	26	0.9		23.40		
	Data Rate	2337.00				Sqm	783.18	2337.00	1830292.00
7	Providining & fixing precaste solid concrete kerb stones of size 450X200X400mm maid out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. KPWD S.R 2018-19 .Item no 5.29.1, Page no 27								
		No's							
	G.Ramaiah Layout								
	1st Cross Road								
	LHS		1	90.3			90.30		
	RHS		1	109			109.00		
	2nd Cross Road								
	LHS		1	102.5			102.50		
	RHS		1	113.9			113.90		
	3rd Cross Road								
	LHS		1	157			157.00		
	RHS		1	128			128.00		
	4th Cross Road								
	LHS		1	119			119.00		
	RHS		1	146.9			146.90		
	4th A Cross Road								
	LHS		1	22			22.00		
	RHS		1	25.5			25.50		
	4th B Cross Road								
	LHS		1	44			44.00		
	RHS		1	47.5			47.50		
	Subash Chandra Bose Layout,Sai Nagar								
	5th Cross Road								
	LHS		1	115			115.00		
	RHS		1	115			115.00		
	6th Cross Road								
	LHS		1	125			125.00		
	RHS		1	125			125.00		
	3rd Cross Road BHEL Layout								
	RHS		1	120			120.00		
	Subash Chandra Bose Layout,Sai Nagar Main Rd								
	RHS		1	30			30.00		
							1735.60		
	Basic Rate	450.00				No's	3857.00	477.00	1839789.00
	Area Weightage @ 6%	27.00							
	Total	477.00							
8	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No.180,I.NO 24.1 of PW,P)								
		Sqm							
	G.Ramaiah Layout								

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	1st Cross Road								
	LHS								
	RHS		1	90.3		0.4	36.12		
	2nd Cross Road		1	109		0.4	43.60		
	LHS								
	RHS		1	102.5		0.4	41.00		
	3rd Cross Road		1	113.9		0.4	45.56		
	LHS								
	RHS		1	157		0.4			
	4th Cross Road		1	128		0.4	51.20		
	LHS								
	RHS		1	119		0.4	47.60		
	4th A Cross Road		1	146.9		0.4	58.76		
	LHS								
	RHS		1	22		0.4	8.80		
	4th B Cross Road		1	25.5		0.4	10.20		
	LHS								
	RHS		1	44		0.4	17.60		
	Subash Chandra Bose Layout,Sai Nagar		1	47.5		0.4	19.00		
	5th Cross Road								
	LHS								
	RHS		1	115		0.4	46.00		
	6th Cross Road		1	115		0.4	46.00		
	LHS								
	RHS		1	125		0.4	50.00		
	3rd Cross Road BHEL Layout		1	125		0.4	50.00		
	RHS								
	Subash Chandra Bose Layout,Sai Nagar Main Rd		1	120		0.4	48.00		
	RHS								
	Subash Chandra Bose Layout,Sai Nagar Main Rd		1	25		0.4	10.00		
	RHS								
	Cross Road		1	30		0.4	12.00		
			1	100		0.4	40.00		
			1	60		0.4	24.00		
			1	45.5		0.4	18.20		
						Sqm	723.64	84.80	61365.00
	Basic Rate	80.00							
	Area Weightage @ 6%	4.80							
	Total	84.80							
9	KSRRB M300-14. Excavation for road work in all type of soil by mechanical means including cutting loading to tippers trimming bottom and side slopes in accordance with requirment of lines and cross sections and transportation with a lead of 1.00 km and complete as per specification. (P.No.143,I.N0 19.14 of PW,P)								
	New Roads		Cum						
	G Ramaiah								
	Main Road		1	385	5.5	0.30	635.25		
	1st Cross		1	180	5.5	0.30	297.00		
	2nd Cross		1	190	5.4	0.25	256.50		
	3rd Cross		1	195	5.4	0.25	263.25		
	4th Cross		1	95.8	5.4	0.25	129.26		
						Cum	1581.26	57.03	90176.00
	Basic Rate	41.00							
	5km Lead	12.80							
	Sub total	53.80							
	Area Weightage @ 6%	3.23							
	Total	57.03							
10	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications. MORTH / Chapter 3								
	New Roads		Sqm						
	G Ramaiah								
	Main Road		1	385	5.5		2117.50		
	1st Cross		1	180	5.5		990.00		
	2nd Cross		1	190	5.4		1026.00		
	3rd Cross		1	195	5.4		1053.00		
	4th Cross		1	95.8	5.4		517.05		
						Sqm	5703.55	6.36	36275.00
	Basic Rate	6.00							
	Area Weightage @ 6%	0.36							
	Total	6.36							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
11	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	New Roads								
	G Ramaiah						Cum		
	Main Road								
	1st Cross		1	385	5.5	0.15	317.63		
	2nd Cross		1	180	5.5	0.15	148.50		
	3rd Cross		1	190	5.4	0.15	153.90		
	4th Cross		1	195	5.4	0.15	157.95		
			1	95.8	5.4	0.15	77.56		
						Cum	855.53	1855.00	1567013.00
	Basic Rate	1750.00							
	Area Weightage @ 6%	105.00							
	Total	1855.00							
12	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	New Roads						Cum		
	G Ramaiah								
	Main Road		1	385	5.5	0.23	487.03		
	1st Cross		1	180	5.5	0.23	227.70		
	2nd Cross		1	190	5.4	0.23	235.98		
	3rd Cross		1	195	5.4	0.23	242.19		
	4th Cross		1	95.8	5.4	0.23	118.92		
						Cum	1311.82	2001.28	2625312.00
	Basic Rate	1888.00							
	Area Weightage @ 6%	113.28							
	Total	2001.28							
13	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	New Roads						Sqm		
	G Ramaiah								
	Main Road		1	385	5.5		2117.50		
	1st Cross		1	180	5.5		990.00		
	2nd Cross		1	190	5.4		1026.00		
	3rd Cross		1	195	5.4		1053.00		
	4th Cross		1	95.8	5.4		517.05		
						Sqm	5703.55	33.92	193464.00
	Basic Rate	32.00							
	Area Weightage @ 6%	1.92							
	Total	33.92							
14	KSRRB 500--10 Providing and applying tack coat using 80/100 grade Sqm bitumen(VGIO) in boiler fitted with spray set distributor at the rate of 0.25 kg per Sqm on the existing prepared bituminous surface cleaned with mechanical broom, complete as per specifications. clause 503 of MORTH V revision. (P-158, Item no 21.7).								
	New Roads						Sqm		
	G Ramaiah								
	Main Road		1	385	5.5		2117.50		
	1st Cross		1	180	5.5		990.00		
	2nd Cross		1	190	5.4		1026.00		
	3rd Cross		1	195	5.4		1053.00		
	4th Cross		1	95.8	5.4		517.05		
						Sqm	5703.55	12.72	72549.00
	Basic Rate	12.00							
	Area Weightage @ 6%	0.72							
	Total	12.72							
15	KSRRB 500-11. Providing and laying bituminous macadam on Prepared Surface with crushed Coarse aggregates as per Design mix formulae for base/binding course including loading of aggregates with F.E loader,Hot mixing of Stone aggregates and bitumen in Hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve desired density, but excluding cost of primer/Tack coat including lead, lift and cost of all materials, labour HOM of machinaries complete as per Specifications. MORTH Ch 5. using 40/60 TPH capacity HMP with Mechanical paver Gr-II (50mm - 75mm) with 3.4% VG-30 bitumen.(P.No-159,I No-21.11.6)								

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	New Roads								
	G Ramaiah								
	Main Road						Cum		
	1st Cross		1	385	5.5	0.05	105.88		
	2nd Cross		1	180	5.5	0.05	49.50		
	3rd Cross		1	190	5.4	0.05	51.30		
	4th Cross		1	195	5.4	0.05	52.65		
			1	95.8	5.4	0.05	25.85		
							Cum 285.18	5962.50	1700371.00
	Basic Rate	5625.00							
	Area Weightage @ 6%	337.50							
	Total	5962.50							
16	KSRRB M500-19: providing and laying bituminous concrete 40mm thick with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification 30-45mm compacted thicikness (GradingII) With 6% bitumen 80/100, No. 161/ Item No. 21.22.1/ PWD SR 2018-19								
	New Roads						Cum		
	G Ramaiah								
	Main Road		1	385	5.5	0.04	84.70		
	1st Cross		1	180	5.5	0.04	39.60		
	2nd Cross		1	190	5.4	0.04	41.04		
	3rd Cross		1	195	5.4	0.04	42.12		
	4th Cross		1	95.8	5.4	0.04	20.68		
							Cum 228.14	8822.04	1967049.00
	Basic Rate	8134.00							
	Area Weightage @ 6%	488.04							
	Total	8622.04							
							Cum		
17	KSRRB M800-13. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (Page No 181., I.No.24.15 of KPWD S.R 2015-16).								
	New Roads						Sqm		
	G Ramaiah								
	Main Road		2	385	0.1		77.00		
	1st Cross		2	180	0.1		36.00		
	2nd Cross		2	190	0.1		38.00		
	3rd Cross		2	195	0.1		39.00		
	4th Cross		2	95.8	0.1		19.15		
							Sqm 209.15	454.74	95109.00
	Basic Rate	429.00							
	Area Weightage @ 6%	25.74							
	Total	454.74							
18	KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97 – DO III Dt 11.06. 997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer.								
	New Roads						Nos		
	G Ramaiah								
	Main Road		2	48			96.00		
	1st Cross		2	23			46.00		
	2nd Cross		2	23			46.00		
	3rd Cross		2	24			48.00		
	4th Cross		2	12			24.00		
							Nos 260.00	357.22	92877
	Basic Rate	337.00							
	Area Weightage @ 6%	20.22							
	Total	357.22							

Sl No	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
22							Grand Total		17066860
23	For 12% Applicable GST								2048023
24	For 4% KRIDL Charges								682674.4
25	For 1% DPR and PMC Charges								200000
	Miscellaneous Charges	L/S							2442.6
Certificate:									20000000
1	The work spot has been inspected and the work is found necessary								
2	This estimate is prepared as per PWD SR of 2018-19								
3	The provisions were made in this estimate are necessary and adequate								
4	This works come under B.B.M.P. limits								

Junior/Assistant Engineer

AE-3

Executive Engineer
Yelahanka Division

ಸಹಾಯಕ ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಉಪವಿಭಾಗ
ಯಲಹಂಕ ಉಪವಿಭಾಗ, ಬೆಂಗಳೂರು-106
Yelahanka Sub Division

Transheight Consultants Pvt. Ltd. Bangalore

Administrative Sanction for Rs. 200.00 lakhs
Two Crore only
is accorded under head P-3749
CM - Navanagarothana 110-Village grants Annexure-07
Registered as CE No. ..... Subject to conditions contained in
No EE/YNK/61/2019-20 Dt. 7/11/2019

Executive Engineer

Technical Sanction
Accorded For Rs 200 lakhs
Head of A/C P-3749
CER NO :203 Dt. 05.11.2019

AE CE (YNK)